

project Workcenter

Materials & Hardware

A	Feet/Support Faces (8)	$\frac{3}{4}$ x 5 - 21	• (42) #8 x $1\frac{1}{2}$ " Fh Woodscrews
B	Feet/Support Spacers (8)	$\frac{3}{4}$ x 5 - 8	• (16) #10 x 4" Fh Woodscrews
C	Foot Pads (3)	$\frac{1}{2}$ x $2\frac{1}{4}$ - 3	• (8) #8 x $\frac{3}{4}$ " Sheet Metal Screws
D	Leveler Rod (1)	$\frac{1}{2}$ "-13 x 6	• (2) $\frac{1}{2}$ "-13 Hex Lock Nuts
E	Upright Faces (4)	$\frac{3}{4}$ x 5 - 25	• (2) $\frac{1}{2}$ " Flat Washers
F	Upright Centers (2)	$\frac{3}{4}$ x 5 - 35	• (2) $\frac{1}{2}$ "-13 x 5" Carriage Bolts
G	Box Sides (2)	9 x 33 - $\frac{3}{4}$ Ply.	• (2) 3" Rigid Casters
H	Box Bottom (1)	$3\frac{1}{2}$ x $28\frac{1}{2}$ - $\frac{3}{4}$ Ply.	• (2) $\frac{5}{8}$ " Self-Aligning Washer Set
I	Shelf (1)	16 x 33 - $\frac{3}{4}$ Ply.	• (10) $\frac{5}{8}$ "-8 Acme Nuts
J	Runners (2)	$\frac{5}{8}$ x $\frac{3}{4}$ - $15\frac{3}{4}$	• (2) $\frac{5}{8}$ " Flat Washers
K	Anchor Blocks (2)	3 x $3\frac{1}{2}$ - 5	• (1) Socket Leveler
L	Traveler Blocks (2)	3 x $3\frac{1}{2}$ - 5	• (1) $\frac{1}{2}$ "-13 Hex Nuts
M	Clamp Rods (2)	$\frac{5}{8}$ "-8 x $22\frac{3}{8}$	• (1) $\frac{1}{2}$ "-13 Knob w/Insert
N	Fixed Top (1)	6 x 38 - $1\frac{1}{2}$ Ply.	• (2) Crank Handles
O	Adjustable Top (1)	8 x 38 - $1\frac{1}{2}$ Ply.	• (2) $\frac{3}{16}$ " x 1" Roll Pins

Cutting Diagram

$\frac{3}{4}$ " x $5\frac{1}{2}$ " - 96" POPLAR (2 Boards @ 3.7 Bd. Ft. each)




$\frac{3}{4}$ " x $5\frac{1}{2}$ " - 96" POPLAR (2 Boards @ 3.7 Bd. Ft. each)



$\frac{3}{4}$ " x $5\frac{1}{2}$ " - 96" POPLAR (3.7 Bd. Ft.)



$\frac{3}{4}$ " x $5\frac{1}{2}$ " - 36" POPLAR (1.4 Bd. Ft.)



NOTE: FOOT PADS (C) ARE PLANED DOWN TO $\frac{1}{2}$ " THICK

60" x 60" - $\frac{3}{4}$ " BALTIC BIRCH PLYWOOD

